LIMEROCK BEARING RATIO TEST REPORT

TEST RESULTS (FM 5-515)			MATERIAL DESCRIPTION
Max. Dry Dens. (pcf)	Opt. Moist (%)	Max. LBR (%)	Dark Brown Sandy Lean Clay w/ Organics & Rubble
117.6	9.9	30.9	

Project No. P2318-2015 **Client:** Berthoud County
Project: Berthoud County Landfill Expansion.
Source of Sample: B-3   **Depth:** 0-5'
Sample Number: S-1

Remarks:
Received 10/30/2015

ALV ENGINEERS

Figure FM-2A

Tested By: ERK   **Checked By:** ALV